



भारत सरकार – रेल मंत्रालय
अनुसंधान अभिकल्प और मानक संगठन
लखनऊ – 2226011
EPBX (0522) 2451200
Fax (0522) 2458500

Government of India – Ministry of Railways
Research Designs & Standards Organisation
Lucknow – 226011
DID (0522) 2450115
DID (0522) 2465310



PROVISIONAL SPEED CERTIFICATE FOR OPERATION

No.	TM/HM/S082/Inspection Vehicle /DFCCIL	Date	As Signed
-----	---------------------------------------	------	-----------

(A) महाप्रबन्धक (इंजीनियरिंग),

1. मध्य रेलवे, छत्रपति शिवाजी टर्मिनस, मुम्बई– 400001
2. पूर्व रेलवे, फेयरली प्लेस, कोलकाता– 700001
3. उत्तर रेलवे, बडौदा हाऊस, नईदिल्ली– 110001
4. पूर्वोत्तर रेलवे, गोरखपुर– 273001
5. पूर्वोत्तर फ्रन्टियर रेलवे, मालीगौव, गुवाहाटी– 781011
6. दक्षिण रेलवे, एनेक्सी, पार्कटाऊन, चेन्नई– 600003
7. दक्षिण मध्य रेलवे, रेलनिलायम, सिकन्दराबाद– 500071
8. दक्षिण पूर्व रेलवे, गार्डनरीच, कोलकाता– 700043
9. पश्चिम रेलवे, चर्चगेट, मुम्बई– 400020
10. उत्तर मध्य रेलवे, प्रयागराज– 211001
11. उत्तर पश्चिम रेलवे, जयपुर– 302006
12. पूर्व मध्य रेलवे, हाजीपुर– 844101
13. पूर्व तट रेलवे, रेलवे कॉम्प्लेक्स, भुवनेश्वर– 751023
14. दक्षिण पश्चिम रेलवे, हुबली– 580023
15. पश्चिम मध्य रेलवे, जबलपुर– 482001
16. दक्षिण पूर्व मध्य रेलवे, बिलासपुर– 495004

(B) प्रबन्ध निदेशक,

डेडीकेटेड फ्रेट कोरीडोर कॉर्पोरेशन ऑफ इण्डिया लि0 पाँचवा तल, प्रगति मैदान मेट्रो स्टेशन बिल्डिंग
कॉम्प्लेक्स नई दिल्ली–110001

Sub:	Provisional Speed Certificate for operation of Inspection Vehicle, Model “MM IC” (Transportation Code RIV D) supplied by M/s Mermec, Italy upto maximum speed of 60kmph when running on its own power as well as when running in train formation over Indian Railways and over routes of Eastern & Western dedicated freight corridors of DFCCIL.
-------------	---

Ref:	DFCCIL Contract Agreement No. (HQ/EN/PWC/PHASE I/PKG-PE-P6/D&B/11/Mitsui) dated 16.11.2020.
-------------	---

1.0 IMPORTANT PARAMETERS RELATED TO ROLLING STOCK

Type	Final / Provisional / Oscillation Trial / COCR Movement	Provisional	Validity / Period or Permanent	IR / Sectional / DFCCIL	5years / IR & Eastern & Western DFCCIL routes.
------	---	-------------	--------------------------------	-------------------------	--

Stock Name	Inspection Vehicle, Model “MM IC”	Max. Axle Load (Empty)	15.1t	Max. Axle Load (Loaded)	16.41t
-------------------	-----------------------------------	-------------------------------	-------	--------------------------------	--------

Transportation Code	RIV D	GA Drg. No.	M/s. SAN Drg. No. SNSK4933 Rev-05
----------------------------	-------	--------------------	-----------------------------------

Bogie Arrgt. Drg. No.	M/s. SAN Drg. No. SNSK4909-Rev-01	Suspension Arrgt. Drg. No.	M/s. SAN Drg. No. DMU-DPC-0-5-001 (Alt. U)
------------------------------	-----------------------------------	-----------------------------------	--

Commodity	Coal / Ore / Steel /Bagged / Oil /etc.	NA	Gauge	BG
------------------	--	----	--------------	----

Type of Bogie	Fabricated	Type of Coupler	Transition Center Buffer Coupler	Wheel Dia. (mm)	New 952	Worn 877
----------------------	------------	------------------------	----------------------------------	------------------------	-------------------	--------------------

Max. Permissible Speed for IR & for routes of Eastern & Western DFCCIL	Own Power	60kmph	Train Formation	60kmph
---	------------------	--------	------------------------	--------

2.0 INTRODUCTION

2.1	Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy as per their GA Drg. No. SNSK4933 Rev-05 is a self-propelled vehicle and is used for visual inspection of the track.
2.2	Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy is having maximum axle load, rigid wheel base and wheel diameter of 16.41t, 2896mm and 952mm respectively. The suspension arrangement is as per M/s. SAN Drg. No. DMU-DPC-0-5-001 (Alt. U). The design speed of machine is 100kmph when running on its own power as well as when running in train formation as a dead vehicle and as a last vehicle. The design details are given in Annexure- A.

3.0	Based on design features, details given in Annexure-A and Dynamic simulation results of Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, it is certified that the machine as per their GA Drg. No. SNSK4933 Rev-05 may be permitted provisionally to run up to maximum permissible speed of 60kmph when running on its own power as well as when running in train formation as a dead vehicle and as a last vehicle for operation over Indian Railways and over routes of Eastern & Western Dedicated Freight Corridors of DFCCIL, subject to the following conditions:-
------------	---

3.1	TRACK				
3.1.1	FOR INDIAN RAILWAYS				
3.1.1.1	The track shall be to a minimum standard of-				
	Rail Section	Sleeper Density	Ballast Cushion	Max. Speed (Own Power)	Max. Speed (Train Formation)
	52 kg (72UTS)	1540 Nos./km PSC Sleeper	250mm (100mm clean & rest in caked up condition on compacted and stable formation)	60kmph	60kmph
3.1.1.2	Track geometry standards shall be maintained to as per provisions of Indian Railways Permanent Way Manual, June-2020, containing track geometry standards under Para 522.				
3.1.1.3	For track maintained to lower standard than that mentioned above, the Chief Engineer shall decide the lower maximum permissible speed on the basis of maintenance condition. In this connection, instructions issued by Railway Board letter no. 65/WDO/SR/26 dated 19/20.10.1966 may be seen. When the Chief Engineer considers that the road bed is not compacted or there is improper drainage, he may suitably restrict the maximum permissible speed depending upon the local conditions.				
3.1.1.4	The maximum permissible speed on curves shall be decided on the basis of the existing provisions of the Indian Railways Permanent Way Manual, June-2020. Maximum cant deficiency permitted would be 75mm.				
3.1.1.5	The welds shall be protected by joggled fish plates as per provisions of USFD Manual and Indian Railways Permanent Way Manual, June-2020 and other policy instructions of Railway Board. The maintenance of Rails and Rail joints shall be ensured as per provisions of Indian Railways Permanent Way Manual, June-2020. In addition, wherever condition warrants on account of corrosion on rail/weld collar, wear on rail, cupping of welds etc., necessary precautions shall be taken for fish plating/joggled fish plating.				
3.1.1.6	Zonal Railways shall ensure further detailed examination of track as deemed fit based on age cum condition basis, overdue renewal and condition of formation etc. as per provisions of Indian Railways Permanent Way Manual, June-2020, regarding permanent way renewals and shall suitably restrict maximum speed of operation based on such examination.				

3.1.2	FOR EASTERN & WESTERN DEDICATED FREIGHT CORRIDORS OF DFCCIL					
3.1.2.1	The track structure shall be of minimum standard-					
	Rail Section	Sleeper Density		Ballast Cushion	Max. Speed (Own Power)	Max. Speed (Train Formation)
	60 kg	1660	Nos./km	300mm (200mm clean &	60kmph	60kmph

	(90 UTS) PSC sleeper test in caked up condition on compacted and stable formation)		
3.1.2.2	The minimum standard of track geometry maintenance shall be as per provisions of Indian Railways Permanent Way Manual, June-2020, containing track geometry standards under Para 522.		
3.1.2.3	For track maintained to lower standard than that mentioned above, the Chief Engineer/GGM (Engg.) concerned shall decide the lower maximum permissible speed on the basis of maintenance condition. In this connection, instructions issued by Railway Board's letter no. 65/WDO/SR/26 dated 19/20.10.1966 may be seen. When the Chief Engineer/GGM (Engg.) considers that the road bed is not compacted or there is improper drainage, he shall suitably restrict the maximum permissible speed depending upon the local conditions.		
3.1.2.4	The maximum permissible speed on curves shall be decided on the basis of the existing provisions of the Indian Railways Permanent Way Manual, June-2020. Maximum cant deficiency permitted would be 75mm.		
3.1.2.5	The welds shall be protected by joggled fish plates as per provisions of USFD Manual and Indian Railways Permanent Way Manual, June-2020 and other policy instructions of Railway Board. The maintenance of Rails and Rail joints shall be ensured as per provisions of Indian Railways Permanent Way Manual, June-2020. In addition, wherever condition warrants on account of corrosion on rail/weld collar, wear on rail, cupping of welds etc., necessary precautions shall be taken for fish plating/joggled fish plating.		
3.1.2.6	DFCCIL shall ensure further detailed examination of track as deemed fit based on age cum condition basis, overdue renewal and condition of formation etc. as per the provisions of Indian Railways Permanent Way Manual, June-2020 regarding permanent way renewals and may suitably restrict maximum speed of operation based on such examination.		

3.2	BRIDGE STIPULATIONS				
3.2.1	FOR INDIAN RAILWAYS				
3.2.1.1	The clearance refers to “Standard RDSO Spans” bridges with standard design of girders, slabs, pipe culverts, piers and abutments etc. issued by RDSO for BGML, RBG, MBG and 25t loading-2008 standard loadings.				
3.2.1.2	Superstructures & Bearings of “Special Spans” (designed and constructed by Zonal Railways based on site requirements), Arches and sub-structures (including foundation) of all bridges (Standard RDSO spans & Special Spans) are to be got examined by the Chief Bridge Engineer and certified safe with respect to current Indian Railway Standard Codes with up to-date correction slips.				
3.2.1.3	The clearance is subject to the following parameters of Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy:-				
	Rolling Stock	Maximum axle load (t)	Maximum tractive effort per axle (t)	Maximum braking force at rail level per axle (t)	Maximum CG height from rail level (mm)
	Inspection Vehicle, Model “MM IC”	16.41	1.07	6.44	1475
3.2.1.4	All Standard RDSO spans of BGML, RBG, MBG and 25t loading-2008 loading are fit for proposed speed of 60kmph when running on its own power as well as when running in train formation.				
3.2.1.5	During operation of Inspection Vehicle, Model “MM IC” with single/multiple locomotives and other rolling stocks, the speed certificate issued by RDSO of the single/multiple locomotives/rolling stocks in empty/loaded condition shall be strictly complied with. Therefore, speed certificate of each single/multiple locomotive and rolling stocks in train formation should be examined carefully & speed restriction/strengthening/prohibition/any other restriction should be imposed according to most restrictive rolling stock/locomotive/multiple locomotives in train formation.				
3.2.1.6	Location of bridges on which speed restrictions are imposed should be notified by the Railways and incorporated in the working timetable.				
3.2.1.7	The final speed on bridges shall also be governed by the track structure on the bridges. Therefore, the lower of the two speeds i.e. speed on particular bridges and speed for track structure over those particular bridges shall prevail as the running speed.				
3.2.1.8	The above para have been arrived at considering bridges are in physically sound condition. In case the bridges are not in satisfactory physical condition, necessary speed restriction to be imposed by Chief Bridge Engineer of Zonal Railway on condition basis.				

3.2.2	FOR EASTERN & WESTERN DEDICATED FREIGHT CORRIDORS OF DFCCIL				
3.2.2.1	The clearance refers to “Standard RDSO Spans” bridges with standard design of girders, slabs, pipe culverts, piers and abutments etc. issued by RDSO for “DFC loading (32.5t axle load)”.				
3.2.2.2	Superstructures & Bearings of “Special Spans” (designed and constructed by DFCCIL based on site requirements), Arches and sub-structures (including foundation) of all bridges (Standard RDSO spans & Special Spans) are to be examined by DFCCIL and certified safe with respect to current Indian Railway Standard Codes with up to-date correction slips.				
3.2.2.3	The clearance is subject to the following parameters of Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy:-				
	Rolling Stock	Maximum axle load (t)	Maximum tractive effort per axle (t)	Maximum braking force at rail level per axle(t)	Maximum CG height from rail level (mm)
	Inspection Vehicle, Model “MM IC”	16.41	1.07	6.44	1475
3.2.2.4	All Standard RDSO spans of DFC loading are fit for proposed speed of 60kmph when running on its own power as well as when running in train formation.				
3.2.2.5	During operation of Inspection Vehicle, Model “MM IC” with single/multiple locomotives and other rolling stocks the speed certificate issued by RDSO of the single/multiple locomotives/rolling stocks in empty/loaded condition shall be strictly complied with. Therefore, speed certificate of each single/multiple locomotive and rolling stocks in train formation should be examined carefully & speed restriction/strengthening/prohibition/any other restriction should be imposed according to most restrictive rolling stock/locomotive/multiple locomotives in train formation.				
3.2.2.6	Location of bridges on which speed restrictions are imposed should be notified by DFCCIL and incorporated in the working timetable.				
3.2.2.7	The final speed on bridges shall also be governed by the track structure on the bridges. Therefore, the lower of the two speeds i.e. speed on particular bridges and speed for track structure over those particular bridges shall prevail as the running speed.				
3.2.2.8	The above para have been arrived at considering bridges are in physically sound condition. In case the bridges are not in satisfactory physical condition, necessary speed restriction to be imposed by DFCCIL on condition basis.				

3.3	SIGNALLING STIPULATIONS
3.3.1	Provisions of GR, SR, IRSOD, DFC-SSOD, SEM & all extant instructions issued from time to time as applicable shall be complied with.
3.3.2	In case of locomotive/rolling stocks /train (having this machine in its composition) having EBD of more than 1 km and non-provision of second distant signal/4 Aspect Automatic signalling in the section, action as per para 7.8.9 of IRSEM (issue July 2021) shall be taken.
3.3.3	While running through a station yard, speed of the Rolling stock shall be restricted to the maximum permissible speed as per standard of interlocking provided at the station or any other speed restriction whichever is severe.

3.4	ROLLING STOCK STIPULATIONS
3.4.1	Before initiating the operation of the Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy the Chief Engineer/Track Machine of the concerned Railway/CGM (Civil Engg.) of the DFCCIL shall ensure the safety of the rolling stock and certify the track worthiness. He shall ensure the proper maintenance of the rolling stock.
3.4.2	Brake of the Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy shall be in perfect working condition during the operation.

3.5	TRACTION INSTALLATION
3.5.1	FOR INDIAN RAILWAYS
3.5.1.1	In 25KV AC traction area, the Principal Chief Electrical Engineer of the concerned Railway shall have to ensure that the minimum height of contact wire and electrical clearances as stipulated in provisions of Chapter-V and V-A, Electric Traction ‘Schedule of Dimensions of 1676mm Gauge (BG) revised 2022’ with latest Addendum & Corrigendum Slips is not violated and strictly followed to ensure its safe running.
3.5.1.2	In addition to above, the Principal Chief Electrical Engineer of the concerned Railway may impose any temporary speed restriction on the basis of personal knowledge, experience of the

	sectional OHE and the field conditions prevailing on the particular section.
3.5.1.3	When the Inspection Vehicle, Model "MM IC" is being moved, it shall be ensured that all the protruding parts are withdrawn and suitably locked, so that during the run there is no possibility of any infringement occurring to the standard moving dimensions.

3.5.2	FOR EASTERN & WESTERN DEDICATED FREIGHT CORRIDORS OF DFCCIL
3.5.2.1	In 25 KV AC traction area, the GGM (Electrical) of the DFCCIL shall have to ensure that the minimum height of contact wire and electrical clearances as stipulated in provisions of Chapter VII of Eastern Corridor & Chapter XIV of Western Corridor, Electric Traction 'Standard Schedule of Dimensions' for dedicated freight corridors with latest Addendum & Corrigendum Slips is not violated and strictly followed to ensure its safe running.
3.5.2.2	In addition to above, the GGM (Electrical) of DFCCIL may impose any temporary speed restriction on the basis of personal knowledge, experience of the sectional OHE and the field conditions prevailing on the particular section.
3.5.2.3	When the Inspection Vehicle, Model "MM IC" is being moved, it shall be ensured that all the protruding parts are withdrawn and suitably locked, so that during the run there is no possibility of any infringement occurring to the standard moving dimensions.

3.6	GENERAL STIPULATIONS
3.6.1	The working of Maintenance Machine shall be as per provision of Indian Railways Permanent Way Manual, June-2020.
3.6.2	The profile of Inspection Vehicle, Model "MM IC" supplied by M/s Mermec, Italy as per their GA Drg. No. SNSK4933 Rev-05 does not infringe to any clause of Chapter IV (D) of Indian Railways Schedule of Dimensions (BG) Revised, 2022 and chapter IV of Eastern Dedicated Freight Corridor & chapter XI of Western Dedicated Freight Corridor for BG 'Standard Schedule of Dimension of Indian Railways, January-2013'.
3.6.3	All the permanent and temporary speed restrictions in force and those that shall be imposed from time to time due to track, bridges, curves, signalling and interlocking etc. shall also be observed. In this connection, the speed on curve shall be in accordance with para 3.1.1.4 for Indian Railway Track and para 3.1.2.4 for DFCCIL track of this speed certificate.
3.6.4	In case of emergency, the machine shall be attached with passenger/goods trains and operation speed of passenger/goods trains shall not be more than 60kmph.
3.6.5	For the movement of the machine, in case of failure of the machine in block sections, the instructions of the para 708(4) of Indian Railways Track Machine Manual, September -2019 shall be followed.
3.6.6	Competent track machine staff who can apply the machine brakes in case of train parting shall escort the machine while running in train formation as a dead vehicle.
3.6.7	This speed certificate is provisional and shall be valid up to 5 years from date of issue or before date of issuance of relevant final speed certificate, whichever is earlier. This Speed Certificate is valid only for Inspection Vehicle, Model "MM IC" supplied by M/s Mermec, Italy coming under DFCCIL Contract Agreement No. (HQ/EN/PWC/PHASE I/PKG-PE-P6/D&B/11/Mitsui) dated 16.11.2020.

ENCLOSURES:/ संलग्नक:

i)	Annexure-A
ii)	M/s. SAN GA Drg. No. SNSK4933 Rev-05.
iii)	Bogie arrangement: M/s. SAN Drg. No. SNSK4909 Rev-01.
iv)	Suspension arrangement: M/s. SAN Drg. No. DMU-DPC-0-5-001 (Alt. U).
v)	DFCCIL letter No. HQ/ENWC/PWC(PnE)/1/2020(6106) dated 13.02.2024.
vi)	Railway Board's letter No. 65/WDO/SR/26 dated 19/20.10.1966.
vii)	Para 708(4) of Indian Railways Track Machine Manual, September -2019.
viii)	Para 704 of Indian Railways Track Machine Manual, September -2019.

(नितिन मेहरोत्रा)

कार्यकारी निदेशक मानक/चालन शक्ति

प्रतिलिपि:

1. सचिव, {यांत्रिक/विद्युत/इंजीनियरिंग(जी)}, रेलवे बोर्ड, रेल भवन, नई दिल्ली- 110001
2. मुख्य रेल संरक्षा आयुक्त, अशोक मार्ग, लखनऊ-226001
3. महाप्रबन्धक(यांत्रिक/विद्युत/संचालन/संकेत एवं दूर संचार)
 - i) मध्य रेलवे, छत्रपति शिवाजी टर्मिनस मुम्बई- 400 001
 - ii) पूर्व रेलवे, फेयरली प्लेस, कोलकाता- 700 001
 - iii) उत्तर रेलवे, बडौदा हाऊस, नई दिल्ली- 110001
 - iv) पूर्वोत्तर रेलवे, गोरखपुर- 273001
 - v) पूर्वोत्तर फ्रन्टियर रेलवे, मालीगाँव, गुवाहाटी- 781 011
 - vi) दक्षिण रेलवे, एनेक्सी, पार्क टाऊन, चेन्नई- 600 003
 - vii) दक्षिण मध्य रेलवे, रेल निलायम, सिकन्दराबाद- 500 071
 - viii) दक्षिण पूर्व रेलवे, गार्डन रीच, कोलकाता- 700 043
 - ix) पश्चिम रेलवे, चर्चगेट, मुम्बई- 400020
 - x) उत्तर मध्य रेलवे, प्रयागराज- 211 001
 - xi) उत्तर पश्चिम रेलवे, जयपुर- 302 006
 - xii) पूर्व मध्य रेलवे, हाजीपुर- 844 101
 - xiii) पूर्व तट रेलवे, रेलवे कॉम्प्लेक्स, भुवनेश्वर- 751 023
 - xiv) दक्षिण पश्चिम रेलवे, हुबली- 580 023
 - xv) पश्चिम मध्य रेलवे, जबलपुर- 482 001
 - xvi) दक्षिण पूर्व मध्य रेलवे, बिलासपुर- 495 004
4. अध्यक्ष एवं प्रबन्ध निदेशक, कोंकण रेलवे कारपोरेशन लिमिटेड, बेलापुर भवन, सेक्टर-11, सी.बी.डी.बेलापुर नवी मुम्बई-400614.
5. जी.जी.एम (मेकैनिकल/इंजी/यातायात/संकेत एवं दूर संचार) डेडीकेटेड फ्रेट कोरीडोर कॉर्पोरेशन ऑफ इण्डिया लि0 नई दिल्ली-110001.

ENCLOSURES:/ संलग्नक:

i)	Annexure-A
ii)	M/s. SAN GA Drg. No. SNSK4933 Rev-05.
iii)	Bogie arrangement: M/s. SAN Drg. No. SNSK4909 Rev-01.
iv)	Suspension arrangement: M/s. SAN Drg. No. DMU-DPC-0-5-001 (Alt. U).
v)	DFCCIL letter No. HQ/ENWC/PWC(PnE)/1/2020(6106) dated 13.02.2024.
vi)	Railway Board's letter No. 65/WDO/SR/26 dated 19/20.10.1966.
vii)	Para 708(4) of Indian Railways Track Machine Manual, September -2019.
viii)	Para 704 of Indian Railways Track Machine Manual, September -2019.

Digitally Signed by Nitin

Mehrotra

Date: 26-07-2024 12:48:02

Reason: Approved

(Signed)
(नितिन मेहरोत्रा)


कार्यकारी निदेशक मानक/चालन शक्ति

Annexure-A

Salient features of Inspection Vehicle, Model “MM IC” supplied by M/s Mermec, Italy.


SN	Description	Details
1.	Principal dimensions of rolling stock	<p>M/s. SAN GA Drg. No. SNSK4933 Rev-05.</p> <p>a. Length over buffers : 22210mm</p> <p>b. Bogie centre distance : 14783mm</p> <p>c. Wheel base : 2896mm</p> <p>d. Max. axle load : 16.41t</p> <p>e. Max. design speed-</p> <p>i) Own power : 100kmph</p> <p>ii) Train formation : 100kmph</p> <p>f. Weight : 65.2t</p>
2.	Bogie and wheel details	<p>M/s. SAN Drg. No. SNSK4909 Rev-01</p> <p>Wheel dia : -</p> <p>New : 952mm</p> <p>Worn : 877mm</p>
3.	Suspension arrangement details	M/s. SAN Drg. No. DMU-DPC-0-5-001 (Alt. U).
4.	Brake system details	Twin Pipe (FP & BP) Air Brake System as per M/s. SAN Drg. No. SNSK4938 Rev-0.
5.	Coupler and Buffer details	<p>Coupler : Transition Center Buffer Coupler</p> <p>Buffer : RDSO SKETCH- 98145</p>
6.	Engine details	<p>Engine Make: Cummins</p> <p>Model: QSN 14 R</p> <p>Power: 400HP @2100 rpm</p>
7.	Safety Items	As per Para 704 of Indian Railways Track Machine Manual, September -2019.

5) * INDICATES NO SEPARATE DRAWINGS

[illegible]

UNDERSLUNG ARRANGEMENTS

This diagram illustrates the internal mechanical layout of the locomotive, viewed from the side. It shows the engine, boiler, and various mechanical components, with numbered callouts for identification. The components are arranged in a symmetrical fashion around the central boiler. The callouts include: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.



	05	WORKSHEET ROTATED. ADDED ITEMS 102&103. ITEM 97 MOVED	21.06.2023	MERMEC
11343	04	BOM QUANTITY & VIEW# CORRECTED, VEHICLE END VIEW MODIFIED.	15.06.2023	KVA
11310	03	REVISÉ & REDRAWN AS PER CUSTOMER REQUIREMENTS.	30.05.2023	KVA
11150	02	REVISÉ & REDRAWN AS PER INTEGRATION OF INSTRUMENTATION ITEMS	15.12.2022	KVA
10550	01	REVISÉ & REDRAWN.	20.09.2021	KVA
ECN. NO.	REV	DESCRIPTION	DATE	INTL.


अनिल कुमार शर्मा / Anil Kumar Sharma
संयुक्त प्रबंधक / संपत्ति प्रबंधक / पश्चिमी कोरिडोर
Jt. General Manager / Asset Management / WDFC
डेडीकेटेड फ्रेट कोरिडोर कॉर्पोरेशन ऑफ इण्डिया लि.
Dedicated Freight Corridor Corporation of India Ltd.
भारतीय रेलवे (रेल मंत्रालय) की एनर्प्राइस
भारतीय रेलवे (Ministry of Railways) Enterprise

DETAILS OF TRACTION POWER PACK EQUIPMENTS				
SL. NO	DESCRIPTION	MAKE	RATING	QTY / VEHICLE
1	ENGINE	CUMMINS	400HP @ 2100 RPM	QSN 14 R 2
2	TRANSMISSION	AMTEC	TC-80	CNT-5533 2

MAX. MOVING DIMENSIONS
WESTERN CORRIDOR
DIAGRAM No. 4
1676mm GAUGE


MAX. MOVING DIMENSIONS
EASTERN CORRIDOR
DIAGRAM No. 4
1676mm GAUGE

MAX. MOVING DIMENSIONS
1D [EDO/T-2202] 1676mm GAUGE
ACS No.27




VIEW-A


100%



SECTION C-C



SECTION D-D



SECTION E-E

MEASURING EQUIPMENTS / OTHER ITEMS [MERMEC SCOPE]			
ITEM NO.	DESCRIPTION	QTY	UNIT
A	1 TVSS [TRACK VIDEO SURVEILLANCE SYSTEM]	2	
B	2 TVSS JUNCTION BOX	2	
B	1 TLS [TRAIN LOCALIZATION SYSTEM] ENCODER	1	
B	2 TLS ENCODER JUNCTION BOX	1	
C	3 TLS ANTENNA	2	
C	3 ACCESS POINT ANTENNA	2	
D	SERVER CABINET [D1]	1	
E	ELECTRICAL CABINET [E1]	1	
F	1 WATER TANK + PUMP FOR WASHING UNIT	1	
F	2 CONTROL UNIT FOR WASHING UNIT	1	
F	3 WASHING SYSTEM INTERCONNECT ASSEMBLY	1	
F	4 FLOW MANIFOLD	1	
G	5 ELECTROVALVE	2	
G	ROOF JUNCTION BOX	2	
H	FIBRE OPTIC BOX	2	
I	1 MONITOR MOUNTING STRUCTURE (SINGLE MODULE)	1	
I	2 DESKTOP COMPUTER / WORKSTATION	1	
I	1 PROJECTION CARTER	1	

101	AXLE EARTHING
100	SPEED SENSOR
99	OHE SENSOR
98	FLOOD LIGHT
97	FLASHER LIGHT (ELRS/SPEC/FL/0017, REV-1, SEPT-04)
96	MARKER LIGHT
95	HEAD LIGHT (RDSO/2017/EL/SPEC/0134, REV-1)
94	PNEUMATIC 2-STAGE HORN
93	WIND SCREEN PNEUMATIC WIPER
92	STONE PROOF LOOKOUT GLASS (ICF/MD/SPEC-159)
91	EXHAUST FAN
90	FAN
89	FOOT STEP LIGHT
88	DOOR FLASHER LIGHT
87	EMERGENCY LIGHT
86	SLOT LIGHT

85	NIGHT LIGHT	5
84	COACH LIGHT [LED TYPE]	28
83	FIRE DETECTION AIR FILTER BOX	1
82	FIRE DETECTION POWER JUNCTION BOX	1
81	FIRE DETECTION JUNCTION BOX	1
80	AIR CONDITIONER SWITCH UNIT	3
79	AIR CONDITIONER CONTROL UNIT	3
78	AIR CONDITIONER [MAKE: COLEMAN]	2
77	AIR CONDITIONER [MAKE: SIDAVAL]	3
76	FOLDABLE SEAT	2
75	DESK SEAT WITHOUT ROTATION [MAKE: SURIN AUTOMOTIVE PVT. LTD - SG10]	1
74	COMPUTER DESK [STAINLESS STEEL WITH CORIAN TOP]	1
73	OFFICERS SEATS WITHOUT ROTATION [MAKE: SURIN AUTOMOTIVE PVT. LTD - SG10]	16
72	DRIVERS SEATS WITH ROTATION [MAKE: SURIN AUTOMOTIVE PVT. LTD - SG10]	4
71	DRIVERS' DESK	2
70	RO WATER PURIFIER	1
69	CHIMNEY	1
68	ELECTRIC HOB	1
67	MICROWAVE OVEN	1
66	FRIDGE	1
65	ROOF WATER TANK [600 LITRES]	2
64	WASH BASIN & MIRROR	1
63	HOT WATER GEYSER [6 LITRES]	2
62	WATER CLOSET, WASH BASIN, HAND SHOWER WITH ACCESSORIES	2 SETS
61	BIO-TOILET	2
60	CABIN INSULATION, 60mm THK [GLASS WOOL INSULATION BLANKET]	1 SET
59	GFRP PANNELLING, 3mm THK	1 SET
58	42" LED TELEVISION	1
57	DINING CHAIR	10
56	DINING TABLE [STAINLESS STEEL WITH CORIAN TOP]	1
55	STORAGE CABINET [STAINLESS STEEL]	6
54	SWIVELLING LADDER	4
53	SNACK TABLE WITH BOTTLE HOLDER	2
52	FOLDABLE BACKREST	4
51	FOLDABLE UPPER BERTH	4
50	LOWER BERTH	4
49	KITCHEN WINDOW WITH WINDOW BARS	1
48	EMERGENCY BREAKABLE WINDOW	2
47	GLASS SEALED WINDOW WITH GRILL	8
46	GLASS SHUTTER WINDOW WITH GRILL	2
45	LAVATORY WINDOW WITH GRILL	2
44	INTERIOR DOORS	9
43	BODY SIDE SWING DOOR	2
42	DRIVER CABIN DOORS	4
41	62.5 kVA GENSET	1
40	CONTROL CUBICLE	1
39	3 kVA TRANSFORMER	1
38	ISOLATION SWITCH	1
37	BATTERY CHARGER	1
36	24 V BATTERY BOX	1
35	9 Litre AIR RESERVOIR	1
34	40 Litre AIR RESERVOIR	2
33	150 Litre AIR RESERVOIR	2
32	AIR DRYER	1
31	AFTER COOLER	2
30	FUEL TANK [1000 LITRES]	1
29	WRA TANK	1
28	ENGINE EXHAUST	2
27	ENGINE AIR CLEANER	2
26	T.C OIL COOLER	2
25	HYDRAULIC OIL COOLER	2
24	HYDRAULIC OIL TANK	2
23	TRACTION ENGINE RADIATOR	1
22	CARDAN SHAFT [1085mm LENGTH]	2
21	CARDAN SHAFT [540mm LENGTH]	2
20	FINAL DRIVE ASSEMBLY	2
19	TRANSMISSION	2
18	ENGINE	2
17	TORQUE ARM ARRANGEMENT	2
16	SECONDARY SUSPENSION SPRINGS	16
15	PRIMARY SUSPENSION HELICAL SPRINGS	16
14	AXLE BOX ASSEMBLY	8
13	WHEEL AXLE ASSEMBLY [POWERED]	2
12	WHEEL AXLE ASSEMBLY [NON-POWERED]	2
11	BOGIE [POWERED]	2
10	COUPLER [RDSO/SB-8D-07]	2
9	SIDE BUFFER [RDSO/SK-98145]	4
8	CATTLE GUARD [WITH ADJUSTABLE RAIL GUARD]	2
7	FOOT STEP FOR LADDER	1
6	FOOT STEP FOR SWING DOOR	2
5	FOOT STEP FOR CABIN DOORS	4
4	ROOF WALKWAY	1 SET
3	LADDER SAFETY GATE	1
2	BODY SIDE LADDER	1
1	BODY SHELL	1
ITEM	DESCRIPTION	QTY / UNIT

GENERAL ARRANGEMENT
OF
INSPECTION CAR

1.50

 **SAN**

**SAN ENGG. AND LOCOMOTIVE
COMPANY LTD.**
BANGALORE - 560 048

DATE	DRG. NO, SNSK4933	REV
07.04.2021		05

NONO FOR TECHNICAL DESIGN PE-P6

Date: _____
 Signature: _____



103	SLIDING DOOR	1	87	EMER
102	SEN SET REMOVAL DOOR	1	86	SPOT

(1) (#): THE CRITICAL LOWEST EQUIPMENT IS FINAL DRIVE WITH MINIMUM RAIL CLEARANCE OF 176mm (WITH NEW WHEEL ø952mm) & 136 5mm (WITH FULLY WORN WHEEL ø877mm) IN LOADED CONDITION.
 (2) DIMENSIONS OF COACH INTERIORS ARE TENTATIVE WHICH WILL HAVE A TOLERANCE DURING ACTUAL DESIGN & MANUFACTURING.
 (3) REVISION 5 EDITED BY MERMEC AFTER MEETING WITH NKC, MITSUI AND MERMEC HELD ON 21/06/2023


- 1) ALL DIMENSIONS ARE IN mm UNLESS STATED OTHERWISE.
2) CODE OF PRACTICE, ABBREVIATION ETC., TO IS : 696.
3) WORK TO COARSE/MEDIUM/FINE TOLERANCES OF IS : 2102 FOR DIMENSIONS WITHOUT TOLERANCE.
4) DO NOT SCALE, IF IN DOUBT PLEASE ASK.

5) * INDICATES NO SEPARATE DRAWINGS.

DRG. NO. SNSK4909



SECTION B-B
90°




SECTION C-C
(1:5)

ITEM-12 TO BE TACK WELDED
AFTER ASSEMBLY

NOTE:

1. FOR SUSPENSION DIAGRAM REFER DRAWING No. SNSK4874.
2. FOR OPEN TOLERANCES & SURFACE FINISH VALUES REFER DRG No. ICF/STD-9-0-001.
3. GALVANISING TO IS:1573 TO SERVICE GRADE No-2 OF TABLE-2.
4. BOLSTER HELICAL SPRINGS TO DRG. NO: SNSK4908.
5. DAMPERS (DOUBLE ACTING HYDRAULIC SHOCK ABSORBERS) TO DRG. NO: ICF/SK-0-5-015, ITEM-2.



VIEW A







अनिल कुमार शर्मा / Anil Kumar Sharma
संयुक्त महाप्रबंधक / संपत्ति प्रबंधक / परिचयी कोरिडोर
Jt. General Manager / Asset Management / WDFC
डेडीकेटेड फ्रेट कोरिडोर कॉर्पोरेशन ऑफ इंडिया लि.
Dedicated Freight Corridor Corporation of India Ltd.
भारत सरकार (रेल मंत्रालय) का उपक्रम

ITEM No.	DRG No.	SIZE	DESCRIPTION	No. OFF	MATL & SPECN
14	SNSK4874	A2	SUSPENSION DIAGRAM FOR 8W RBMV	1	
13	SVIDPC3 0-0-002	A1	FIXING ARRGT OF STOPPER FOR FINAL DRIVE	1	
12	98903050	*	SPRING WASHER B12	4	IS:3063-1994
11		*	HEXAGONAL HEAD SCREW - IS:1363 (PART-2)/ISO: 4018-M12x20L-4.6	4	IS:1363 (PART-2)
10	DC/EMU/M 0-5-011	A3	SAFETY STRAP	2	
9	SNSK4185	A1	TORQUE ARM FIXING ARRGT.	1	
8	DMU/DPC7-3-2-702	A1	BOGIE BRAKE PIPING & PARKING BRAKE ARRGT	1	
7	EMU/M 3-2-064	A1	BOGIE BRAKE ARRANGEMENT	1	
6	DMU/DPC 0-5-001	A1	BOGIE BOLSTER SUSPENSION ARRGT.	1	
5	DMU/DPC 0-4-001	A1	BOGIE BOLSTER ARRANGEMENT	1	
4	SVIDPC3 0-3-001	A1	BOGIE FRAME ARRANGEMENT	1	
3	SVIDPC 0-2-003	A1	ROLLER BEARING ARRGT [NON-POWERED AXLE]	1	
2	SVIDPC 0-2-001	A1	ROLLER BEARING ARRANGEMENT [POWERED AXLE]	1	
1	DHM/DPC 0-1-001	A1	AXLE BOX GUIDE ARRANGEMENT	1	
ITEM No.	DRG No.	SIZE	DESCRIPTION	No. OFF	MATL & SPECN
DRN.	RAM				
TRCD					
CHKD.	GAS				
APPD.	KVA				

BOGIE GENERAL
ARRANGEMENT
FOR INSPECTION
CAR

SCALE
1:10
SAN ENGS. AND LOCOMOTIVE
COMPANY LTD.
BANGALORE - 560 048
DRG. NO. SNSK4909
REV 01

ECN. NO.	REV.	DESCRIPTION	DATE	INTL.	ECN. NO.	REV.	DESCRIPTION	DATE	INTL.
1					2				
3					4				
5					6				
7					8				
9					10				
11					12				



VIEW FROM -B

QTY	DESCRIPTION & DIMENSION	ITEM	REF.DRGS	MAT.SPEC	WEIGHT/UNIT	REMARKS
GROUP: 0-5						
SUPERSEDED BY:						
13-08-2014 26-09-2001						
SCALE: 1:5						
CHD						
ALTD						
DRN						
Alpha AL-0						
INDIAN RAILWAY STANDARDS						
DATA CODE NO. 156						
SHEET 1 OF 2						
DMU/DPC-0-5-001						







TABLE-1

*TABLE OF OR 4/5 SPRING HEIGHT

TYPE OF COACH	C THICKNESS (mm)	No. OF OR PER COACH	D SPRING HEIGHT (mm)
DMU/DPC	11	13	305
DMU/M	17	32	315
MEMU/DMC	21	40	311
DMU/DPC	DMC END	8	324
	N.B.V. END	—	331
DHTC	DMC SIDE	10	322
	PASSENGER SIDE	9	327
DHTC/J	DMC SIDE	13	319
	PASSENGER SIDE	9	323
ARTV/BAN	DMC	6	328
ARTV/KPC	DMC	7	325
RTV/J	DMC	4	328
DMU/M (BANK)	DMC END	21	311
	N.B.V. END	13	319
ARTV/KPC	DMC END	12	330
	N.B.V. END	8	334
DETG	DMC SIDE	18	313
	DMC SIDE	10	323
DETG/AS	DMC SIDE	15	317
	PASSENGER SIDE	12	320
SPURT OR	DMC	21	279
	DMC SIDE	5	295
JOC	DMC SIDE	8	324
	DMC SIDE	18	314

TABLE-2

HARDWARE FOR SHOCK ABSORBER FIXING-QTY REQUIREMENT

	WITH BOLT, NYLOC NUT & PUNCHED WASHER	WITH PREDRILLED BOLT, SPRING LOCK WASHER, NUT & SPLIT PIN
ITEM-28	ITEM-28	ITEM-27
ITEM-29	ITEM-29	ITEM-30
ITEM-31	ITEM-31	ITEM-32
ITEM-33	ITEM-33	ITEM-34
ITEM-35	ITEM-35	ITEM-36
ITEM-37	ITEM-37	ITEM-38
ITEM-39	ITEM-39	ITEM-40
ITEM-41	ITEM-41	ITEM-42
ITEM-43	ITEM-43	ITEM-44
ITEM-45	ITEM-45	ITEM-46
ITEM-47	ITEM-47	ITEM-48
ITEM-49	ITEM-49	ITEM-50
ITEM-51	ITEM-51	ITEM-52
ITEM-53	ITEM-53	ITEM-54
ITEM-55	ITEM-55	ITEM-56
ITEM-57	ITEM-57	ITEM-58
ITEM-59	ITEM-59	ITEM-60
ITEM-61	ITEM-61	ITEM-62
ITEM-63	ITEM-63	ITEM-64
ITEM-65	ITEM-65	ITEM-66
ITEM-67	ITEM-67	ITEM-68
ITEM-69	ITEM-69	ITEM-70
ITEM-71	ITEM-71	ITEM-72
ITEM-73	ITEM-73	ITEM-74
ITEM-75	ITEM-75	ITEM-76
ITEM-77	ITEM-77	ITEM-78
ITEM-79	ITEM-79	ITEM-80
ITEM-81	ITEM-81	ITEM-82
ITEM-83	ITEM-83	ITEM-84
ITEM-85	ITEM-85	ITEM-86
ITEM-87	ITEM-87	ITEM-88
ITEM-89	ITEM-89	ITEM-90
ITEM-91	ITEM-91	ITEM-92
ITEM-93	ITEM-93	ITEM-94
ITEM-95	ITEM-95	ITEM-96
ITEM-97	ITEM-97	ITEM-98
ITEM-99	ITEM-99	ITEM-100
ITEM-101	ITEM-101	ITEM-102
ITEM-103	ITEM-103	ITEM-104
ITEM-105	ITEM-105	ITEM-106
ITEM-107	ITEM-107	ITEM-108
ITEM-109	ITEM-109	ITEM-110
ITEM-111	ITEM-111	ITEM-112
ITEM-113	ITEM-113	ITEM-114
ITEM-115	ITEM-115	ITEM-116
ITEM-117	ITEM-117	ITEM-118
ITEM-119	ITEM-119	ITEM-120
ITEM-121	ITEM-121	ITEM-122
ITEM-123	ITEM-123	ITEM-124
ITEM-125	ITEM-125	ITEM-126
ITEM-127	ITEM-127	ITEM-128
ITEM-129	ITEM-129	ITEM-130
ITEM-131	ITEM-131	ITEM-132
ITEM-133	ITEM-133	ITEM-134
ITEM-135	ITEM-135	ITEM-136
ITEM-137	ITEM-137	ITEM-138
ITEM-139	ITEM-139	ITEM-140
ITEM-141	ITEM-141	ITEM-142
ITEM-143	ITEM-143	ITEM-144
ITEM-145	ITEM-145	ITEM-146
ITEM-147	ITEM-147	ITEM-148
ITEM-149	ITEM-149	ITEM-150
ITEM-151	ITEM-151	ITEM-152
ITEM-153	ITEM-153	ITEM-154
ITEM-155	ITEM-155	ITEM-156
ITEM-157	ITEM-157	ITEM-158
ITEM-159	ITEM-159	ITEM-160
ITEM-161	ITEM-161	ITEM-162
ITEM-163	ITEM-163	ITEM-164
ITEM-165	ITEM-165	ITEM-166
ITEM-167	ITEM-167	ITEM-168
ITEM-169	ITEM-169	ITEM-170
ITEM-171	ITEM-171	ITEM-172
ITEM-173	ITEM-173	ITEM-174
ITEM-175	ITEM-175	ITEM-176
ITEM-177	ITEM-177	ITEM-178
ITEM-179	ITEM-179	ITEM-180
ITEM-181	ITEM-181	ITEM-182
ITEM-183	ITEM-183	ITEM-184
ITEM-185	ITEM-185	ITEM-186
ITEM-187	ITEM-187	ITEM-188
ITEM-189	ITEM-189	ITEM-190
ITEM-191	ITEM-191	ITEM-192
ITEM-193	ITEM-193	ITEM-194
ITEM-195	ITEM-195	ITEM-196
ITEM-197	ITEM-197	ITEM-198
ITEM-199	ITEM-199	ITEM-200
ITEM-201	ITEM-201	ITEM-202
ITEM-203	ITEM-203	ITEM-204
ITEM-205	ITEM-205	ITEM-206
ITEM-207	ITEM-207	ITEM-208
ITEM-209	ITEM-209	ITEM-210
ITEM-211	ITEM-211	ITEM-212
ITEM-213	ITEM-213	ITEM-214
ITEM-215	ITEM-215	ITEM-216
ITEM-217	ITEM-217	ITEM-218
ITEM-219	ITEM-219	ITEM-220
ITEM-221	ITEM-221	ITEM-222
ITEM-223	ITEM-223	ITEM-224
ITEM-225	ITEM-225	ITEM-226
ITEM-227	ITEM-227	ITEM-228
ITEM-229	ITEM-229	ITEM-230
ITEM-231	ITEM-231	ITEM-232
ITEM-233	ITEM-233	ITEM-234
ITEM-235	ITEM-235	ITEM-236
ITEM-237	ITEM-237	ITEM-238
ITEM-239	ITEM-239	ITEM-240
ITEM-241	ITEM-241	ITEM-242
ITEM-243	ITEM-243	ITEM-244
ITEM-245	ITEM-245	ITEM-246
ITEM-247	ITEM-247	ITEM-248
ITEM-249	ITEM-249	ITEM-250
ITEM-251	ITEM-251	ITEM-252
ITEM-253	ITEM-253	ITEM-254
ITEM-255	ITEM-255	ITEM-256
ITEM-257	ITEM-257	ITEM-258
ITEM-259	ITEM-259	ITEM-260
ITEM-261	ITEM-261	ITEM-262
ITEM-263	ITEM-263	ITEM-264
ITEM-265	ITEM-265	ITEM-266
ITEM-267	ITEM-267	ITEM-268
ITEM-269	ITEM-269	ITEM-270
ITEM-271	ITEM-271	ITEM-272
ITEM-273	ITEM-273	ITEM-274
ITEM-275	ITEM-275	ITEM-276
ITEM-277	ITEM-277	ITEM-278
ITEM-279	ITEM-279	ITEM-280
ITEM-281	ITEM-281	ITEM-282
ITEM-283	ITEM-283	ITEM-284
ITEM-285	ITEM-285	ITEM-286
ITEM-287	ITEM-287	ITEM-288
ITEM-289	ITEM-289	ITEM-290
ITEM-291	ITEM-291	ITEM-292
ITEM-293	ITEM-293	ITEM-294
ITEM-295	ITEM-295	ITEM-296
ITEM-297	ITEM-297	ITEM-298
ITEM-299	ITEM-299	ITEM-300
ITEM-301	ITEM-301	ITEM-302
ITEM-303	ITEM-303	ITEM-304
ITEM-305	ITEM-305	ITEM-306
ITEM-307	ITEM-307	ITEM-308
ITEM-309	ITEM-309	ITEM-310
ITEM-311	ITEM-311	ITEM-312
ITEM-313	ITEM-313	ITEM-314
ITEM-315	ITEM-315	ITEM-316
ITEM-317	ITEM-317	ITEM-318
ITEM-319	ITEM-319	ITEM-320
ITEM-321	ITEM-321	ITEM-322
ITEM-323	ITEM-323	ITEM-324
ITEM-325	ITEM-325	ITEM-326
ITEM-327	ITEM-327	ITEM-328
ITEM-329	ITEM-329	ITEM-330
ITEM-331	ITEM-331	ITEM-332
ITEM-333	ITEM-333	ITEM-334
ITEM-335	ITEM-335	ITEM-336
ITEM-337	ITEM-337	ITEM-338
ITEM-339	ITEM-339	ITEM-340
ITEM-341	ITEM-341	ITEM-342
ITEM-343	ITEM-343	ITEM-344
ITEM-345	ITEM-345	ITEM-346
ITEM-347	ITEM-347	ITEM-348
ITEM-349	ITEM-349	ITEM-350
ITEM-351	ITEM-351	ITEM-352
ITEM-353	ITEM-353	ITEM-354
ITEM-355	ITEM-355	ITEM-356
ITEM-357	ITEM-357	ITEM-358
ITEM-359	ITEM-359	ITEM-360
ITEM-361	ITEM-361	ITEM-362
ITEM-363	ITEM-363	ITEM-364
ITEM-365	ITEM-365	ITEM-366
ITEM-367	ITEM-367	ITEM-368
ITEM-369	ITEM-369	ITEM-370
ITEM-371	ITEM-371	ITEM-372
ITEM-373	ITEM-373	ITEM-374
ITEM-375	ITEM-375	ITEM-376
ITEM-377	ITEM-377	ITEM-378
ITEM-379	ITEM-379	ITEM-380
ITEM-381	ITEM-381	ITEM-382
ITEM-383	ITEM-383	ITEM-384
ITEM-385	ITEM-385	ITEM-386
ITEM-387	ITEM-387	ITEM-388
ITEM-389	ITEM-389	ITEM-390
ITEM-391	ITEM-391	ITEM-392
ITEM-393	ITEM-393	ITEM-394
ITEM-395	ITEM-395	ITEM-396
ITEM-397	ITEM-397	ITEM-398
ITEM-399	ITEM-399	ITEM-400
ITEM-401	ITEM-401	ITEM-402
ITEM-403	ITEM-403	ITEM-404
ITEM-405	ITEM-405	ITEM-406
ITEM-407	ITEM-407	ITEM-408
ITEM-409	ITEM-409	ITEM-410
ITEM-411	ITEM-411	ITEM-412
ITEM-413	ITEM-413	ITEM-414
ITEM-415	ITEM-415	ITEM-416
ITEM-417	ITEM-417	ITEM-418
ITEM-419	ITEM-419	ITEM-420
ITEM-421	ITEM-421	ITEM-422
ITEM-423	ITEM-423	ITEM-424
ITEM-425	ITEM-425	ITEM-426
ITEM-427	ITEM-427	ITEM-428
ITEM-429	ITEM-429	ITEM-430
ITEM-431	ITEM-431	ITEM-432
ITEM-433	ITEM-433	ITEM-434
ITEM-435	ITEM-435	ITEM-436
ITEM-437	ITEM-437	ITEM-438
ITEM-439	ITEM-439	ITEM-440
ITEM-441	ITEM-441	ITEM-442
ITEM-443	ITEM-443	ITEM-444
ITEM-445	ITEM-445	ITEM-446
ITEM-447	ITEM-447	ITEM-448
ITEM-449	ITEM-449	ITEM-450
ITEM-451	ITEM-451	ITEM-452
ITEM-453	ITEM-453	ITEM-454
ITEM-455	ITEM-455	ITEM-456
ITEM-457	ITEM-457	ITEM-458
ITEM-459	ITEM-459	ITEM-460
ITEM-461	ITEM-461	ITEM-462
ITEM-463	ITEM-463	ITEM-464
ITEM-465	ITEM-465	ITEM-466
ITEM-467	ITEM-467	ITEM-468
ITEM-469	ITEM-469	ITEM-470
ITEM-471	ITEM-471	ITEM-472
ITEM-473	ITEM-473	ITEM-474
ITEM-475	ITEM-475	ITEM-476
ITEM-477	ITEM-477	ITEM-478
ITEM-479	ITEM-479	ITEM-480
ITEM-481	ITEM-481	ITEM-482
ITEM-483	ITEM-483	ITEM-484
ITEM-485	ITEM-485	ITEM-486
ITEM-487	ITEM-487	ITEM-488
ITEM-489	ITEM-489	ITEM-490
ITEM-491	ITEM-491	ITEM-492
ITEM-493	ITEM-493	ITEM-494
ITEM-495	ITEM-495	ITEM-496
ITEM-497	ITEM-497	ITEM-498
ITEM-499	ITEM-499	ITEM-500
ITEM-501	ITEM-501	ITEM-502
ITEM-503	ITEM-503	ITEM-504
ITEM-505	ITEM-505	ITEM-506
ITEM-507	ITEM-507	ITEM-508
ITEM-509	ITEM-509	ITEM-510
ITEM-511	ITEM-511	ITEM-512
ITEM-513	ITEM-513	ITEM-514
ITEM-515	ITEM-515	ITEM-516
ITEM-517	ITEM-517	ITEM-518
ITEM-519	ITEM-519	ITEM-520
ITEM-521	ITEM-521	ITEM-522
ITEM-523	ITEM-523	ITEM-524
ITEM-525	ITEM-525	ITEM-526
ITEM-527	ITEM-527	ITEM-528
ITEM-529	ITEM-529	ITEM-530
ITEM-531	ITEM-531	ITEM-532
ITEM-533	ITEM-533	ITEM-534
ITEM-535	ITEM-535	ITEM-536
ITEM-537	ITEM-537	ITEM-538
ITEM-539	ITEM-539	ITEM-540
ITEM-541	ITEM-541	ITEM-542
ITEM-543	ITEM-543	ITEM-544
ITEM-545	ITEM-545	ITEM-546
ITEM-547	ITEM-547	ITEM-548
ITEM-549	ITEM-549	ITEM-550
ITEM-551	ITEM-551	ITEM-552
ITEM-553	ITEM-553	ITEM-554
ITEM-555	ITEM-555	ITEM-556
ITEM-557	ITEM-557	ITEM-558
ITEM-559	ITEM-559	ITEM-560
ITEM-561	ITEM-561	ITEM-562
ITEM-563	ITEM-563	ITEM-564
ITEM-565	ITEM-565	ITEM-566
ITEM-567	ITEM-567	ITEM-568
ITEM-569	ITEM-569	ITEM-570
ITEM-571	ITEM-571	ITEM-572
ITEM-573	ITEM-573	ITEM-574
ITEM-575	ITEM-575	ITEM-576
ITEM-577	ITEM-577	ITEM-578
ITEM-579	ITEM-579	ITEM-580
ITEM-581	ITEM-581	ITEM-582
ITEM-583	ITEM-583	ITEM-584
ITEM-585	ITEM-585	ITEM-586
ITEM-587	ITEM-587	ITEM-588
ITEM-589	ITEM-589	ITEM-590
ITEM-591	ITEM-591	ITEM-592
ITEM-593	ITEM-593	ITEM-594
ITEM-595	ITEM-595	ITEM-596
ITEM-597	ITEM-597	ITEM-598
ITEM-599	ITEM-599	ITEM-600
ITEM-601	ITEM-601	ITEM-602
ITEM-603	ITEM-603	ITEM-604
ITEM-605	ITEM-605	ITEM-606
ITEM-607	ITEM-607	ITEM-608
ITEM-609	ITEM-609	ITEM-610
ITEM-611	ITEM-611	ITEM-612
ITEM-613	ITEM-613	ITEM-614
ITEM-615	ITEM-615	ITEM-616
ITEM-617	ITEM-617	ITEM-618
ITEM-619	ITEM-619	ITEM-620
ITEM-621	ITEM-621	ITEM-622
ITEM-623	ITEM-623	ITEM-624
ITEM-625	ITEM-625	ITEM-626
ITEM-627	ITEM-627	ITEM-628
ITEM-629	ITEM-629	ITEM-630
ITEM-631	ITEM-631	ITEM-632
ITEM-633	ITEM-633	ITEM-634
ITEM-635	ITEM-635	ITEM-636
ITEM-637	ITEM-637	ITEM-63

No.: HQ/ENWC/PWC(PnE)/1/2020(6106)

Dated: 13.02.2024

ED/Track Machine
RDSO
Manak Nagar
Lucknow- 226011

Sub: Allotment of Transportation Code to Track Machines supplied by MERMEC.

Ref: Director/Track Machine-VI/RDSO letter no. TM/HM/S082/DFCCIL Dated 01.02.2024

In reference to the referred letter, the submission of corrected documents was sought by your office. In this regard, in continuation to this office letter of even no. dated 30.01.2024, the following additional details/clarifications are being submitted.

S.No.	Name of the Machine	Serial No.	GA Drawing No.
1.	Inspection Vehicle 1	MM800DFCCIL 822/2024	SNSK4933 Rev-5
2.	Inspection Vehicle 2	MM800DFCCIL 823/2024	
3.	Track Recording Car	MM800DFCCIL 820/2024	SNSK4840 Rev-4
4.	OHE Recording Car	MM800DFCCIL 821/2024	SNSK 4932 Rev-4

The earlier proposed Transportation Code and Model No. of the vehicles shall remain unchanged. The Layout Drawing Nos. submitted vide this office letter of even no. dated 30.01.2024 may not be considered please. Only GA Drawings No. may be considered

The details of OHE Recording Car will be sent to TI Directorate/RDSO separately.


(Praveen Kumar)
ED/Asset Mgmt./WDFC



Mr. Praveen Kumar, ED/Asset Mgmt. /WDFC, DFCCIL, New Delhi

Sub: Design, Manufacturing, Supply, Testing, Commissioning & Training of Plant and Equipment for Railway Track and Electric Over Head Equipment (OHE) on Dadri – Rewari - JNPT network of Western Dedicated Freight Corridor (ICB No. PE P-6):– **Regarding Allotment of Transportation Code, serial number and GAD number to Track machines supplied by M/s Mermec.**

Ref: (i) Mitsui letter no. PEP6-MIT-NKC-2024-02-012 dated 09.02.2024
(ii) NKC letter no. L-NKC-MITSUI-PMC-2402-05 dated 02.02.2024
(iii) DFCCIL email dated 01.02.2024 forwarding RDSO letter no. TM/HM/S082/DFCCIL dated 01.02.2024
(iv) DFCCIL letter no. HQ/ENWC/PWC (PnE)/1/2020 (6106) dated 30.01.2024
(v) Mitsui email dated 11.01.2024

Dear Sir,

With reference to the communication from the Employer vide ref. (iii) above, to submit the Engineers response, on the issues raised in RDSO Letter dated 01.02.2024, to send suitable response regarding the Allotment of Transportation Code to Track machine being supplied by M/s Mermec from DFCCIL to RDSO. The details for the M/e Mermec vehicles are shown as under:

S.no.	Name of the Machine	Transportation code	Serial no.	GAD drawing number
1	Track Recording Car	TRC D	MM800DFCCIL 820/2024	SNSK4840 Rev-4
2	OHE Recording Car	ORC D	MM800DFCCIL 821/2024	SNSK4932 Rev-4
3	Inspection Vehicle 1	RIV D	MM800DFCCIL 822/2024	SNSK4933 Rev-5
4	Inspection Vehicle 2		MM800DFCCIL 823/2024	

As per the layout drawing no. mentioned by RDSO, please consider this as the interior layout drawing and not the General arrangement drawing (GAD). As per record GAD remains the same for TRC as SNSK4840 Rev-4, ORC as SNSK4932 Rev-4 and Inspection vehicle as SNSK4933 Rev-5

Thanking You,
Yours faithfully,

Tetsuto Nakano
Project Director
The Engineer for Employer

CC: Mr. Anurag Sharma, CGM/DFCCIL, Jaipur

New Delhi, October 19/20, 1966

To

The General Managers,
All Indian Railways.

The G.M. & Chief Engineer,
Railway Electrification project, Calcutta.

The Chief Administrative Officer,
B.B.K. Railway Projects, Waltair.

Sub: Use of new type of Rolling Stock.

.....

Use of new type of rolling stock on existing Railway systems is governed by the Rules laid down in Chapter VI of the Rules for opening of a Railway. In terms of para 5 of this Chapter, applications for use of new type of rolling stock are required to be accompanied by a certificate to be signed by the Chief Engineer and Chief Mechanical Engineer of a Railway in a form specified therein.

2. The Board wish to point out that this certificate by the Chief Engineer and the Chief Mechanical Engineer (and Chief Electrical Engineer in case of electrical stock) is a positive act of certification in regard to track and locomotive maintenance standards for the speed indicated and a statutory obligation. The Officers signing the certificate are required to decide, on the basis of their personal knowledge and experience of the maintenance conditions of the track, locomotives or rolling stock, with due regard to relevant information available and the maintenance requirements of the new type of rolling stock, as to whether the operation of the particular type of locomotive or rolling stock on the relevant section of the Railway is safe and practicable with the facilities available on the Railway system. The RDSO merely recommend the maximum speed at which locomotives and rolling stock could be permitted to run on standard track under average maintenance conditions and this recommendation is made only on the basis of design features of the particular type of locomotive, rolling stock and assessment of their suitability from oscillation and other tests conducted by the RDSO. These certificates for speed issued by RDSO are meant merely to assist the CEs and CMEs/CEEs in deciding on the speed at which these engines/rolling stock may be permitted to run on their Railway system for the maintenance conditions obtaining on their Rlys.

3. A note on the subject prepared by the DG/RDSO is enclosed herewith in quadruplicate for guidance of your officers.

Receipt of this letter may please be acknowledged.

DA: As above.

No. 65/WDO/SR/26

Sd/-
(B.S.D. Baliga)
Director, Civil Engineering,
Railway Board
New Delhi, October 19/20, 1966,

Copy to D.G. RDSO, Alambagh, Enclosed with reference to his letter No. MRA/573 of 16.8.1966.

Sd/-
(B.S.D. Baliga)
Director, Civil Engineering,
Railway Board.

Enclosure to Board's letter No.65/WDO/SR/26 dated 19-10-66.

....

Use of new types of Rolling Stock.

The rules for use of new types of rolling stock on existing railways are laid down in Chapter VI of the Rules for Opening of a Railway. According to para 5 of this Chapter, applications for use of new type of rolling stock are required to be accompanied by a certificate to be signed by the Chief Engineer and the Chief Mechanical Engineer of the Railway in the form specified in para 5(a)(ii). It should be clearly understood that this certificate by the Chief Engineer and the Chief Mechanical Engineer (Chief Electrical Engineer in the case of Electrical Stock) is a positive act of certification and a statutory obligation.

2. The Chief Engineers and Chief Mechanical Engineers (Chief Electrical Engineers in the case of electric stock) are required to decide on the basis of their personal knowledge and experience of track, locomotives or rolling stock with due regard to relevant information available of track and rolling stock and their maintenance requirements, as to whether the operation of particular locomotive or rolling stock is safe and practicable with the facilities provided on the railway system. It may be emphasized that respective Heads of Departments are required to certify annually regarding the sound condition of the track and rolling stock in operation in terms of para 1222 of Indian Railway Code for Accounts department.

3. Prior to the setting up of testing facilities on the Indian Railways, the safety certificate for operation of locomotives and rolling stock was issued by the Chief Engineer and Chief Mechanical Engineers on the basis of their personal knowledge and experience and on the basis of the recommendation for speed limit by the consulting engineers, who were available. With the build up of increased design and testing facilities in RDSO, due recommendation is made by RDSO on the basis of design features of particular stock and assessment of their stability from oscillation tests conducted on main line track in normal state of maintenance and not subjected to speed restriction.

4. R.D.S.O. advises the Railway of the speed at which different types of locomotive and rolling stock can be permitted to run on different track structures. This is done in two stages.

- (a) preliminary speed; and
- (b) final maximum speed.

The preliminary speed is based on a study of the design characteristics of the vehicle and experience of performance of similar designs in India and/or abroad. Such speed would be generally lower than the sectional maximum speed and it would not be difficult for CEs and CMs to arrive at a decision in issuing the Safety Certificate. Further, it is up to the CEs to decide whether any particular sections or routes require the imposition of a restriction on a generally sanctioned speed. Such a decision has to be based purely on the personal knowledge and experience of the engineers of the zonal railways.

5. It is, however, necessary to keep a watch on the performance of vehicles permitted on such preliminary speed limit to gather experience for guidance in determination of the final maximum speed both by RDSO and Railways the former taking this aspect into account along with the review of the oscillation test, and the latter while issuing the certificate for the final maximum speed.

The final maximum speed is determined by the RDSO on a review of the oscillation tests generally conducted for new designs and on confirmation of the suitability of the stock from the point of view of strength of track and bridges, although such investigation is made even at the initial stage of design. The oscillation trials are conducted with a view to obtaining data relating to the riding characteristics of the vehicle at the specified speeds. Such tests include aspects, such as, vertical wheel/axle load and lateral force ratio and vertical and lateral acceleration of the vehicle. The studies are aimed at assessing the possibilities of track distortion, wheel mounting, riding comforts etc. For conducting these tests, a section of main line track is selected over which there are no temporary restrictions and which is considered by the railway as being in a generally run down condition for main line standards but without speed restriction. The vehicle is tested generally for new and worn clearance conditions and also where relevant for operation in the forward or back-ward direction. The vehicle selected is one of those in average condition of normal maintenance. The tests are conducted on speeds usually 10% higher than that to which it is proposed to be certified.

On the basis of the theoretical and studies and investigations of the tests as indicated and the analysis of the test results, the RDSO recommends the maximum speeds up to which a vehicle can be permitted in normal traffic operation. The certificate of the RDSO though issued by the Director Standards (Mech.) is the final result of studies conducted by the various concerned

Directorates such as Civil Engineering, Carriage and Wagon Motive Power etc. This recommendation of the RDSO is meant to be used as guidance by the CEs and CMs of the zonal railways in formulating their own certificates to be furnished to the ACRS. It is up to Chief Engineer, Chief Mechanical Engineers and Chief Electrical Engineers to consider on the basis of their personal knowledge and experience of track locomotive and rolling stock and their maintenance requirements whether the conditions prevailing are such as to require a reduction in the speed of the vehicles in normal traffic operation.

6. In the case of certification of speeds by the CEs and CMs up to 105 Km/hr., it is neither feasible nor it is considered necessary that any more guidance than that at present being given by RDSO should be available to them in normal cases in arriving at their conclusions in the matter of formulation of their certificates to the ACRS. In the case of operation at higher speeds, it is proposed that in addition to the data at present being furnished, copies of track recording charts of the track over which the tests were conducted would also be incorporated in the test reports and made available for reference to the CEs and CMs. It has already been accepted by the Board that in the case of high speed track (speed above 105 km/hr) track recording would be done at intervals of about 6 months. A comparison of the track recording for the test track with the track recording of the routes over which the high speeds are to be run would be an additional guidance to the CEs and CMs in the formulation of their certificates.

In conclusion, it may be pointed out that the statutory obligation of certification of speeds is that of the CEs and CMs/ and CEs of the zonal railways. In discharging these functions, the CEs and CMs/CEs are assisted by the RDSO. The extent of such assistance would normally depend on the speeds involved and the facilities available with the RDSO. The procedures, at present, followed are considered satisfactory for speeds upto 105 km/hr. For higher speeds, recording of characteristics of the test track would also be made available to the zonal railways for purpose of comparison with the actual track conditions prevailing from time to time.

....

involve large number of labour working with the machine. Hence, extra care is necessary as detailed below, to ensure safety of workers.

- (b) Hooters should be provided on the track machines. These hooters should be used to warn the staff working on/around the track machine about approaching train on adjoining track. Remote controlled hooters shall also be deployed as an added precaution by SSE/JE/P.Way so that lookout man standing around 150 m away from the track machine can also operate the hooter to warn the staff suitably. SSE/JE/TM shall also put on the flasher light on as an added precaution till the train on adjacent line has passed the site of work.
 - (c) Caution order of 30 to 50 kmph with instructions to whistle freely should be imposed on the adjacent line, during the duration of block, for the safety of workmen, depending upon the site conditions and visibility.
- (8) **Checking Infringement After Work** - The vertical and lateral clearance for OHE, signal post and any other structure should be checked and adjusted before clearing the block. It shall be ensured by SSE/JE (P.Way) working with track machine that there should be no infringement to signal post, OHE and any other structure as per schedule of dimensions.

708 Failure and Accidents of Track Machines

- (1) **Protection in case of Breakdown** - In the event of breakdown, the track machines shall be protected as per GR 6.03 and SR there to by the machine staff, as directed by machine in-charge.
- (2) **Failures in Block Section** - Failures in block sections of the track machines will be treated as accident under class 'J – Equipment failure'.
- (3) **Accidents involving Track Machine** - Accidents involving track machines shall be treated as train accidents under the appropriate class and action shall be taken as per the rules in force.
- (4) **Action in case of Failure in Block** - In case of failure of track machine in block section, immediate information with details should be conveyed to the ADEN/DEN/Sr.DEN of the section and the AXEN/XEN/Dy.CE/Line/TM. SE/JE/TM should decide in consultation with SSE/JE (P. Way), the action to be taken to clear the section. They may decide to push the disabled unit to the nearest station provided the brake power is in good condition. Otherwise, intimation shall be sent to the nearest Station Master asking for a light engine to tow the unit.
- (5) **Request for ART/Breakdown** - In case, SSE/JE (P. Way) and/or SSE/JE/TM feels clearance of section is going to take long time, the assistance of Road Breakdown or Accident Relief Train shall be asked for immediately. Meanwhile SSE/JE/TM in-charge on the machine shall take necessary action to rectify the defect(s). SSE/JE (P. Way) shall provide all necessary assistance.

certificate. Machine competency certificate is to be issued to SSE/JE/TM by Dy.CE/TM Line or an officer authorized by him. This certificate will be issued as per proforma given in **Annexure 7.3** after ascertaining the successful completion of technical training, G & SR training and his medical fitness. The validity of this certificate will be up to the earliest expiry date of the three i.e. (i) Technical training (ii) G & SR training and (iii) PME.

For automatic block section, separate competency is required to be issued as per the practice in the Zonal Railway.

704 Safety Equipment

- (1) **General** - SSE/JE/TM in-charge shall be responsible to ensure that the following equipment in working condition are available on the track machine:
 - (a) Two red and one green hand signal flags.
 - (b) Two tri-colour hand signal lamps /LED torch.
 - (c) Two chains with padlocks.
 - (d) One fire extinguisher in each cabin.
 - (e) Two hooters (manually controlled).
 - (f) Two jacks 10 t.
 - (g) Four wooden blocks.
 - (h) Four crow bars.
 - (i) One hydraulic hand pump.
 - (j) Emergency pneumatic/hydraulic hose of sizes suiting to different machines (Complete with end fitting).
 - (k) Wire rope with close loops at both ends 2 m and 9 m long for BCM: One of each length.
 - (l) Machine specific equipment, if any, listed in Chapter 2, 3, 4 and 5.
 - (m) Ten fog signals (detonators) in a tin case.
 - (n) A copy of the working timetable of the section where the machine is working.
 - (o) G & SR book with up to date amendment slips.
 - (p) One 4 cell flasher light LED lamp cum flasher light (rechargeable).
 - (q) Two banner flags.
 - (r) One first aid box.
 - (s) Two skids.
 - (t) Safety helmets for all machine staff.
 - (u) Protective clothing, safety shoes and safety gloves.
 - (v) Walkie talkie with frequency of SM, Guard and Loco Pilots.

- (w) Internal communication system like walkie-talkie and/or head mounted system.
 - (x) Track Machine Manual with up to date correction slips.
 - (y) Accident Manual.
 - (z) Tail lamp.
- (2) **Head and Tail Lights** – Each track machine must be equipped with prescribed head and tail lights, marker lights and flasher lights as per GR 4.14, 4.15 & 4.16 and SRs thereof. Each machine shall display LV board/tail lamp when moving alone. While moving in conveyor coupled, the LV board/tail lamp shall be fixed on the last vehicle; in the direction of movement.

705 Rules for Operation – General

- (1) **Stabling of Track Machines** - When the track machine(s) is/are stabled at a station, SSE/JE/TM in-charge shall ensure that it is clear of fouling marks and traps and necessary precautions against rolling down such as pinning down hand brakes, chaining and provision of skids; is taken in accordance with G&SR.
- (2) **Shunting of Track Machines** - No track machine shall be moved between a running line and the siding/stabling line without the written permission of the Station Master on duty in the form of shunting order/shunt signals.
- (3) **Machine Ready Memo** - SSE/JE/TM shall issue a written machine ready memo (as per Annexure 7.4) after necessary maintenance/repairs/schedules and Brake Power testing and other stipulated checks, if any, to on duty SM, indicating time and date, under advice to SSE/JE/P.Way deputed to work with the machine.
- (4) **Movement of Track Machines** - When the track machine is required to move from one station to another station, SSE/JE/TM shall run the machine only with proper authority to proceed and all necessary permits, notices and cautions as specified in G&SR. When track machine is to move on wrong road (against the direction of traffic), the speed of track machine shall not exceed more than 25 kmph and flasher light shall be kept "ON".
- (5) **Working in Group**
 - (a) When more than one machine is required to work within the same block section, these machines may be allowed to move into the block section in a group under one authority as detailed in this chapter. In such situation all the track machines must leave and enter the section simultaneously one after another keeping adequate distance among them and with proper authority as detailed further in the following paras.
 - (b) Total number of the machines shall be clearly mentioned in the line clear/block authority message with exchange of private numbers. For